

Ref: Technical Specs – Emeralda One

<u>Technical Specifications for "Emeralda One"- Agios Athanasios</u> Plot 481

1. PRELIMINARY WORKS

- a. Architectural plans & structural design
- b. Liability for all building permissions
- c. Lining of the constructions
- d. Preparations of contracts
- e. Supervision from a qualified architect
- f. Clean to prepare the house to be delivered

2. EARTHWORKS

a. Earthworks according to the plans to ensure all the finish levels inclusive compaction, compressor.

3. STRUCTURE

a. The tunnel system form is applied for the construction of the structure. Continuous vertical reinforced concrete columns together with horizontal reinforced concrete slabs, form a monolithic structure with ant-seismic abilities according to drawings

4. WALLING

- a. External walls are constructed with 250mm thick.
- b. Internal walls are constructed with 100mm thick.

5. WALL FINISHING & PLASTERING

- a. Internal walls are rendered with three coats of spatula and emulsion paint white color.
- b. External walls are decorated according to the designers / owner / architect's preference; close to the façade.

6. FLOORING

- a. Living room, dining room & entry hall tiles has an allocated budget of 25€.
- b. Bedroom tiles has an allocated budget of $25 \in$.
- c. Kitchen tiles has an allocated budget of $25 \in$.
- d. Veranda tiles has an allocated budget of $25 \in$.
- e. Bathroom ceramic tiles has an allocated budget of 25€.
- f. Common area staircase has an allocated budget of 1,000€ per staircase / stage.
- g. Common area quality tiles with an allocated budget of 25€.
- h. Tile dimensions should be 60 cm * 60 cm or 60 cm * 120 cm.
 - Charges are applicable to changes.
 - Prices are per m2.
 - Prices are VAT inclusive.

7. WALL TILES

- a. Kitchen ceramic tiles has an allocated budget of $25 \in$.
- b. Bathroom floor / wall ceramic tiles has an allocated budget of 25€.
- c. Tile dimensions should be 60 cm * 60 cm or 60 cm * 120 cm.
 - Charges are applicable to changes.
 - Prices are per m2
 - Prices are VAT inclusive

8. DOORS & WINDOWS

- a. Apartment main entrance doors are melamine embossed with an allocated budget of 800€.
- b. Apartment main entrance doors are fire resistant
- c. The apartment's internal doors are melamine embossed.
- d. Main door handle is at 25€ each. (VAT Inclusive)
- e. All external doors and windows are with aluminum & double glazing series 3000 thermal (color according to the designer's/architect's preference).

9. WARDROBES & KITCHEN UNITS

- a. Kitchen unit: 250€ per running meter.
- b. Wardrobes with doors: 250€ per sq. m
 - Prices are VAT inclusive

10. SANITARY WARE FITTINGS

- a. Bathtub, W/C, washbasin, mixed taps, fittings, kitchen composite double sink (2,000€ for one bedroom & 2,500€ for the two bedroom)
 - Prices are VAT inclusive

11. PLUMBING-DRAINAGE

- a. Hot & cold water installation includes plastic storage tanks & high pressure system (pipe in pipe).
- b. Complete Solar System.

12. ELECTRICAL

- a. Includes an adequate number of lighting power, TV, telephone points, bell, and cooker control. Lightning fixtures are not included.
 - Charges are applicable on extra lightning outlets.

13. AIR CONDITIONING

a. Provisions only

14. PHOTOVALTICS

a. Provisional installation.

15. PARKING AREA

- a. Made of concrete
- b. Parking bar with a remote control
- c. Fully waterproofed
- d. Proper fencing and boundary walls shall be surrounding the project. (Refer to the façade)

16. ROOF & ROOF GARDEN

- a. Construction shall be completed according to the architectural plans.
- b. Fully waterproofed & tiled.
- c. Glass & Aluminum parapets.

17. ENTRANCE

a. Door phone for each apartment.

b. Luxuriously designed with care to unveil the beauty of the building through minimalistic false ceiling designs, and lavish ceramic tiling.

18.WATERPROOFING

a. Full waterproofing for exposed areas and wet areas (GF, parking floors, roof, top of roof, bathrooms, garden areas).

19. LIFT

a. High-end Lift. (Brand TBD)